

# Underground Mobile Home Entrance Requirement

## PVC SIZE (SCHEDULE 80)

200 AMP - 2 1/2"

100 AMP - 2 1/2"

Approved electrical PVC conduit

## Wire Size

200 AMP - 2/0 Copper or 4/0 Aluminum

100 AMP - #4 Copper or #2 Aluminum

\* 4 Wire Service Required From Disconnect Box To All Mobile Homes and Modulars

2 1/2" Male Adapter  
Plus Lock Ring and Bushing

2 1/2" PVC Schedule 80 minimum  
Gray In Color  
(For REMC Entrance Wire)

